


15-065-62879-06-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rush County. Sec. 9 Twp. 6 Rge. 22 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines NW NE NE
Lease Owner Musgrove Petroleum Corporation
Lease Name RUSH Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Well
Date well completed August 24 19 50
Application for plugging filed September 14 19 53
Application for plugging approved September 14 19 53
Plugging commenced September 30 19 53
Plugging completed September 30 19 53
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production July 19 19 53
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas.
Producing formation Lansing- Kansas City Depth to top 3490' Bottom unknown Total Depth of Well 3663 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	156'	
				5-1/2"	3660 1/2'	2730'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3551' to 3500'.
Dumped 4 sacks cement from 3500' to 3468'. Filled hole with mud to 155'. Set 10' rock bridge with 15 sacks cement. This brought it up from 145' to 100'. Filled with mud from 100' to 35' and set 5' rock bridge from 35' to 30'. Mixed and ran 10 sacks cement from 30' to bottom of seller.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Jayhawk Casing Pulling Company,
Address Russell, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
GORDON L. KOELLING (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of October 19 53

My commission expires September 24, 1956.

Thelma L. Stumpp
Notary Public.

PLUGGING
FILE SEC 9 T 6 R 22a
BOOK PAGE 128 LINE 30

RECEIVED
STATE CORPORATION COMMISSION
OCT - 6 1953
CONSERVATION DIVISION
Wichita, Kansas
10-6-53