

15-065-00065-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

GRAHAM

County. Sec. 9 Twp. 6 Rge. 22 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines ~~NW NW NE~~ NE NW NE

Lease Owner B & R DRILLING, INC.

Lease Name RUSH

Well No. # 1

Office Address RUSSELL, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) OIL

Date well completed June 27, 1947 19

Application for plugging filed September 20, 1949 Verbally 19

Application for plugging approved September 20, 1949 Verbally 19

Plugging commenced September 20, 1949 19

Plugging completed September 26, 1949 19

Reason for abandonment of well or producing formation All Oil recovered.

If a producing well is abandoned, date of last production September 24, 1949

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well ELDON PETTY

Producing formation Depth to top Bottom Total Depth of Well 3873' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	220'	None
				5 1/2"	3706'	2435'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging Record

Filled hole with crushed rock from 3533' to 3500'. Dumped 5 sax cement at 3500' with dump bailer, top of cement at 3460'. Filled with mud to 220', set rock bridge, dumped 15 sax cement, top of cement 170' Filled with mud to 35'. Dumped 10 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to B & R DRILLING, INC.
Address RUSSELL, KANSAS

10-5-49

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

DON ROBERTS

(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

RUSSELL, KANSAS

(Address)

SUBSCRIBED AND SWORN to before me this 3 rd day of OCTOBER, 19 49.

My commission expires 6/17/50

22-5133-s 9-48-10M

PLUGGING
FILE SEC 9 T 6 R 202
BOOK PAGE 117 LINE 21

Notary Public.