

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20812-00-02  
Spot: NWSE Sec/Twnshp/Rge: 20-30S-33W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: WILLET ESTATE Well #: 1-20  
County: HASKELL Total Vertical Depth: 5570 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: PO BOX 18496 6200 N WESTERN AVE.  
OKLAHOMA CITY, OK 73154

MSCC Size: feet: 3040 WITH 375 SX CMT CIRC  
PROD Size: 4.5 feet: 5426 WITH 300 SX CMT  
SURF Size: 8.625 feet: 1817 WITH 750 SX CMT #18103

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/11/2005 9:30 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: RANDY GRAYSON Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PUMP 300# HULLS WITH 30 SX CMT. PUMP 65 BBL SPACER TO 1850'. 210 SX CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND  
Date/Time Plugging Completed: 03/17/2005 2:00 PM

Witness Type: COMPLETE (100%)  
KCC Agent: JIM HOLLAND

Actual Plugging Report:

3/11/05: PUMP 300# HULLS WITH 30 SX CMT. PUMP 65 BBL MUD SPACER TO 1850', PUMP 270 SX CMT (SAW PRESSURE @ 140 SX) 5 1/2" ON VACUUM AT END OF JOB. LET CMT FALL & TAG TOP OF CMT. PUMPED 8 SX CMT ON BACKSIDE. PRESSURED TO 500 PSIG & SHUT IN. 3/17/05: TAG CMT @ 1400'. PUMP 125 SX CMT DOWN 5 1/2". FILLED FROM 1400' TO SURFACE. STAYED FULL. 5 1/2" CASING FULL OF CMT FROM APPROXIMATELY 3700' TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
5249	5371		

RECEIVED  
MAR 30 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed Jim Holland PART II  
(TECHNICIAN)

INVOICED  
DATE 4-4-05  
INV. NO. 2005061344

Form CP-2/3