

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23293-00-00  
Spot: SWSENE Sec/Twnshp/Rge: 25-21S-14W  
2310 feet from N Section Line, 1050 feet from E Section Line  
Lease Name: PETERS Well #: 1  
County: STAFFORD Total Vertical Depth: 3766 feet

Operator License No.: 32639  
Op Name: CORAL PRODUCTION CORPORATION  
Address: 1600 STOUT STREET, SUITE 1500  
DENVER, CO 80202

SURF Size: 8.625 feet: 365

#12240

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/23/2005 7:00 PM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 3700' WITH 50 SX CMT. 2ND PLUG AT 860' WITH 40 SX CMT. 3RD PLUG AT 380' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 03/23/2005 10:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:


1ST PLUG AT 3700' WITH 50 SX CMT. 2ND PLUG AT 860' WITH 40 SX CMT. 3RD PLUG AT 380' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED  
MAR 30 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: DP

District: 01



Signed

Michael Maier  
(TECHNICIAN)

INVOICED

DATE

4-4-05

INV. NO.

2005061345

Form CP-2/3