

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24829-00-00
Spot: NWSENESW Sec/Twnshp/Rge: 31-16S-13W
1770 feet from S Section Line, 2040 feet from W Section Line
Lease Name: CARTER Well #: 3
County: BARTON Total Vertical Depth: 3507 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

SURF Size: 8.625 feet: 408

#113⁹⁸

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/28/2005 2:00 AM
Plug Co. License No.: 9431 Plug Co. Name: VONFELDT DRILLING, INC
Proposal Rcvd. from: DOUG BUDIG Company: GLM COMPANY Phone: (785) 735-4142

Proposed Plugging Method: Ordered out 180 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 03/28/2005 8:40 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

1st. Plug at 3400' w/25 sxs.
2nd. Plug at 930' w/40 sxs.
3rd. Plug at 489' w/80 sxs.
4th. Plug at 40' w/10 sxs - 8 5/8" wiper plug.

RECEIVED
MAR 30 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 4-4-05

INV NO. 2005061355

Form CP-2/3

MAR 28 2005