

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-22199-00-00
Spot: SESWNW Sec/Twnshp/Rge: 6-23S-4E
3034 feet from S Section Line, 4419 feet from E Section Line
Lease Name: WEDEL Well #: 3-C
County: BUTLER Total Vertical Depth: 2536 feet

Operator License No.: 32444
Op Name: HIZEY SERVICE & SUPPLY, INC.
Address: BOX 296
AUGUSTA, KS 67010

PROD Size: 4.5 feet: 2535 100 SX CMT
SURF Size: 8.625 feet: 201 165 SX CMT

8242

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/08/2005 1:00 PM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING
Proposal Rcvd. from: MIKE KISER Company: HIZEY SERVICE & SUPPLY, INC. Phone: (316) 775-5496

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/08/2005 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded back 50' above perforations with 4 sacks of cement on top of sand. Shot and pulled casing to surface. Ran 1" tubing to 250' and circulated cement to surface with 100 sacks of 60/40 posmix with 4% gel.

Cementing by Braden Petroleum

Perfs:

Top	Bot	Thru	Comments
2455	2464		
RECEIVED KCC DISTRICT #2 MAR 15 2005 WICHITA, KS			
RECEIVED APR 01 2005 KCC WICHITA			

Remarks:

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

INVOICED
DATE 4-4-05
INV. NO. 2005061348