

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-00578-00-00
Spot: SWNESW Sec/Twnshp/Rge: 7-18S-9W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: KINEMOND Well #: 2
County: RICE Total Vertical Depth: 3240 feet

Operator License No.: 31528
Op Name: KELSO, MIKE - OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

PROD Size: 5.5 feet: 3230 75 SX CMT
SURF Size: 8.625 feet: 198 100 SX CMT

#105³⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/15/2005 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Sand perms to 2980' & put 5 sxs cement on top;
Plugging cut off 5-1/2";
Method: pull to 1200' & pump 35 sxs;
pull casing to 850' & pump 35 sxs;
and pull casing to 250' & circ cement to surf.

Plugging Proposal Received By: MICHAEL WILSON
Date/Time Plugging Completed: 03/15/2005 1:00 PM

WitnessType: PARTIAL
KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2980' and put 5 sacks of cement on top.
Cut off casing at 1518'.
Pulled casing to 1200' and pumped 35 sacks of cement.
Pulled casing to 850' and pumped 35 sacks of cement.
Pulled casing to 250' and circulated cement to surface.

Allied Cement #20653

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3223	3229		
3063	3066		
3044	3047		
3030	3034		

RECEIVED
KCC DISTRICT #2
MAR 17 2005
WICHITA, KS

RECEIVED
APR 01 2005
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 4.4.05

INV. NO. 2005061350