

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21517-00-01
Spot: NWNWSE Sec/Twnshp/Rge: 5-31S-33W
2292 feet from S Section Line, 2325 feet from E Section Line
Lease Name: GASKILL Well #: 5-5
County: SEWARD Total Vertical Depth: 5650 feet

Operator License No.: 9228
Op Name: MARLIN OIL CORPORATION
Address: PO BOX 14630
OKLAHOMA CITY, OK 73113

CIBP Size: feet: 4170 WITH 2 SX CMT
MSCC Size: feet: 2911 WITH 500 SX CMT CIRC
PROD Size: 5.5 feet: 5649 WITH 575 SX CMT
SURF Size: 8.625 feet: 1865 WITH 900 SX CMT

4/83⁶³

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/21/2005 10:30 AM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 4170'. PLUG AT 1880' WITH 25 SX CMT. PLUG AT 800' WITH 90 SX CMT TO 0'.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/21/2005 12:30 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

SET CIBP @ 4170' WITH 2 SX CMT ON TOP. TOP OF FLUID @ 1880'. 1ST PLUG PUMP 25 SX CMT AT 1880'. PUMP 26 BBL MUD SPACER TO 600'. 2ND PLUG PUMP 25 SX CMT TO 400'. PUMP 9 BBL MUD SPACER TO 40'. 3RD PLUG PUMP 10 SX CMT TO SURFACE. HOOK UP TO BACKSIDE. PUMP 10 SX CMT. PRESSURE TO 300 PSIG & SHUT IN.

Perfs:

Top	Bot	Thru	Comments
5338	5342		
5256	5272		
5030	5034		
4782	4788		
4609	4612		
4200	4202		

RECEIVED
MAR 30 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
MAR 23 2005
KCC Dodge City

Signed Jim Holland PIRTH
(TECHNICIAN)

INVOICED
DATE 4-4-05
INV NO. 2005061354

Form CP-2/3