

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-02842-00-00
Spot: E2SEW Sec/Twnshp/Rge: 30-14S-14W
3300 feet from S Section Line, 2970 feet from E Section Line
Lease Name: EHRlich Well #: 3
County: RUSSELL Total Vertical Depth: 3250 feet

Operator License No.: 6622
Op Name: SCHOENBERGER, J.L. D/B/A JASON OIL
Address: PO BOX 701 363 W 12TH ST
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3247 100 SX CMT
SURF Size: 8.625 feet: 160 135 SX CMT

\$105⁶³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2005 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JIM SCHOEBERGER Company: JASON OIL COMPANY Phone: (785) 483-4204

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/14/2005 11:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Tied onto 5 1/2" and pumped 230 sxs 60/40 pozmix - 10% gel cement with 600# hulls.
Cement standing 30 feet from surface.
Max. P.S.I. 400#. S.I.P. 0#.

Perfs:

Top	Bot	Thru	Comments
3247	3250		

RECEIVED
APR 01 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

10 *Case Morris*
(TECHNICIAN)

INVOICED

DATE 4-4-05

INV. NO. 2005061364

Form CP-2/3

MAR 30 2005

JOHN O. FARMER

#3 EHRlich

30-14-14W
E2 SE NW

Contr. CO. TOOLS

RUSSELL County

E. 1821RB Comm. 12/8/62 Comp. 1/31/63 IP 30 BOPD+12 BW/ARB
3247-50

Tops	Depth	Datum
ANH	840	+981
HEEB	2945	-1124
TOR	2961	-1140
LANS	3005	-1184
ARB	3245	-1424
TD	3250	-1429

Casing NO LOG

8" 160/135

5" 3247/100

DST 2972-3036/50", 40' M, BHP

860-480#/20", FP 0-0#


DST 3244-50/1 HR, 630' G, 360' CL

GASY 0, 300' FROG GSY 0, BHP

990-990#/20", FP 0-160#

CO TD: SWB 2 BOPH, NATL

GORHAM



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

11201067