

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23015-00-00
Spot: S2SESE Sec/Twnshp/Rge: 36-18S-25W
330 feet from S Section Line, 660 feet from E Section Line
Lease Name: DICK HORCHEM Well #: 1
County: NESS Total Vertical Depth: 4410 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

MSSC Size: feet: 1750 WITH 325 SX CMT
PROD Size: 5.5 feet: 4404 WITH 150 SX CMT
SURF Size: 8.625 feet: 264 WITH 165 SX CMT

#143³³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2005 11:15 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE J FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: SAND BOTTOM TO 50' ABOVE PERFS & 5 SX CMT. RUN TUBING TO 1750'. CIRCULATE CMT TO SURFACE. PRESSURE ANNULUS TO 500 PSIG WITH CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/24/2005 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SAND BRIDGED OFF AT 3000'. COULD NOT GET THROUGH. CEMENTED WITH 4 SX CMT. RUN TUBING TO 1700' & PUMPED 135 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TUBING & TOPPED OFF WITH 30 SX CMT. TIE ONTO BACKSIDE & PUMP 20 SX CMT. PRESSURED TO 500# & HELD.

Perfs:


Top	Bot	Thru	Comments
4401	4410	OH	
4304	4322		

RECEIVED
MAR 30 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Michael Maier
(TECHNICIAN)

INVOICED
DATE 4-4-05
INV. NO. 2005061361

Form CD-23