

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23037-00-00
Spot: N2NWSW Sec/Twnshp/Rge: 20-8S-22W
2310 feet from S Section Line, 750 feet from W Section Line
Lease Name: QUINT C Well #: 2
County: GRAHAM Total Vertical Depth: 3650 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: P.O. BOX 1469
PLAINFIELD, IL 60544

SURF Size: 8.625 feet: 217

#118⁶³

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/23/2005 1:30 AM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: BURT BEERY Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 03/23/2005 3:30 AM KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 1785' w/25 sxs.
2nd. Plug at 925' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ACID SERVICES, INC.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

INVOICED

DATE 4-4-05
INV. NO. 2005061363

Form CP-2/3

MAR 28 2005