

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03464-00-00
Spot: E2SW Sec/Twnshp/Rge: 26-11S-17W
1320 feet from S Section Line, 2310 feet from W Section Line
Lease Name: HALL B Well #: 17
County: ELLIS Total Vertical Depth: 3555 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

COND Size: 12.5 feet: 100
PROD Size: 5.5 feet: 3549 w/100 sxs cmt
SURF Size: 8.625 feet: 1112

#115

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2005 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 10% gel - 900# hulls - 10 sxs gel.
Casing squeezed at 1167' w/143 sxs cement (1954).
Casing leaks at 140'- 70' (2002).
Casing leaks at 1391' - 1735' (2002).

Plugging Proposal Received By: DENNIS HAMEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2005 5:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perfs:

RIH with tubing to 1500' - hit solid bridge and got tubing hung.
Pulled 10,000# over to pull free.
Pumped 250 sxs cement with 600# hulls with good water - circulated to surface.
Ordered more cement and gel - waited 1.5 hours.
Pulled tubing to 1200' - pumped 10 sxs gel, followed with 80 sxs cement with 300# hulls - had good cement to surface.
POOH with tubing. Squeezed 80 sxs cement down casing with good cement up 8 5/8" S.P.

RECEIVED
MAR 31 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED

DATE 4-4-05
WEL NO. 2005061366

MAR 28 2005

WICHITA
KANSAS
MAOICED

CITIES SERVICE OIL CO

#B-17 HALL

26-11-17W
C EL SW

Contr. _____ ELLIS County

E 2091 Comm. 12-9-40 Comp. 1-2-41 IP 3000 BOPD
ECHO

Tops	Depth	Datum
TOP	3050	
LANS	3310	
ARB	3554	
TD	3555	

Casing
12" 100
8" 1112
5" 3549

2700' OIH/30"
A/5000

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS