

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-03462-00-00  
Spot: NENESW Sec/Twnshp/Rge: 26-11S-17W  
2310 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: HALL B Well #: 15  
County: ELLIS Total Vertical Depth: 3482 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

PROD Size: 5.5 feet: 3468 w/100 sxs cmt  
SURF Size: 8.625 feet: 1060 w/310 sxs cmt

#113<sup>17</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/17/2005 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JOE STULL Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls - 15 sxs gel.  
Squeezed at 1095' - 1102' w/150 sxs (1976).  
Squeezed at 2455' - 3244' w/300 sxs (1976).

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/17/2005 12:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perfs:

RIH with tubing 3380' - spotted 15 sxs gel, followed with 50 sxs cement with 300# hulls and two barrels water.  
Pulled tubing to 1500' - circulated cement to surface with 80 sxs cement.  
POOH with tubing and squeezed casing with 60 sxs cement with good cement to surface up 8 5/8" S.P.  
Shut in and squeezed an additional 30 sxs cement.  
Max. P.S.I. 400#. Shut in 400#.

RECEIVED  
MAR 31 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel  
(TECHNICIAN)

INVOICED

DATE

4-4-05

INV. NO.

2005061366

Form CP-2/3

MAR 28 2005

CITIES SERVICE OIL CO

#B-15 HALL

26-11-17W  
NE NE SW

Contr. \_\_\_\_\_ ELLIS County

E 2012 Comm. 8-24-40 Comp. 9-16-40 IP 3000 BOPD  
ECHO

Tops	Depth	Datum
TOP	2960	
LANS	3220	
ARB	3468	
TD	3482	

Casing  
8" 1060  
5" 3468

2800' OIH: A/1500

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

43016111