

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21906-00-00
Spot: NWSENE Sec/Twnshp/Rge: 9-32S-34W
1900 feet from N Section Line, 1250 feet from E Section Line
Lease Name: DOWNING A Well #: 4
County: SEWARD Total Vertical Depth: 2905 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

CIBP Size: feet: 2661
PROD Size: 4.5 feet: 2902 WITH 420 SX CMT
SURF Size: 8.625 feet: 643 WITH 250 SX CMT

#944

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/16/2005 3:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 100# HULLS & 15 SX CMT. MUD SPACER TO 700'. CIRCULATE WITH CMT FROM 700' TO 0'.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2005 4:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2860'. PUMP 100# HULLS WITH 15 SX CMT. PUMP MUD SPACER TO 700'.
PUMP 55 SX CMT TO SURFACE. PRESSURE TO 500 PSIG & SHUT IN. ANNULUS
VALVE FULL OF CMT, BACKSIDE FULL.

Perfs:


Top	Bot	Thru	Comments
2690	2706		
2665	2673		
2634	2638		

RECEIVED
MAR 30 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED

DATE

4-4-05

WEL. NO.

2005061359

Form CP-243