

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21459-00-01
Spot: NWSWNE Sec/Twnshp/Rge: 27-21S-7W
3792 feet from S Section Line, 2310 feet from E Section Line
Lease Name: STEIERL Well #: 1
County: RICE Total Vertical Depth: 3492 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 5.5 feet: 3491 150 SX CMT
SURF Size: 8.625 feet: 232 200 SX CMT

#113⁴⁹

Well Type: EOR UIC Docket No: E24836.1 Date/Time to Plug: 03/10/2005 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE FUNK Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Sand off perms to 3360' & put 5 sxs cement on top;
Plugging cut off 5-1/2" @ 2500';
Method: pull to 1000' & pump 35 sxs cement;
pull casing to 550' & pump 35 sxs cement;
and pull 280' & circ cement to surf.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 03/10/2005 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3360' and put 5 sacks of cement on top.
Cut off 5-1/2" at 2500'.
Pulled to 1000' and pumped 35 sacks of cement.
Pulled casing to 550' and pumped 35 sacks of cement.
Pulled to 280' and circulated cement to surface.

Copeland Acid & Cement #24952
60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3438	3448		
3432	3436		
3410	3418		

RECEIVED
KCC DISTRICT #2
MAR 17 2005
WICHITA, KS

RECEIVED
APR 01 2005
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 4-4-05
INV. NO. 2005061341