

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20394-00-01
Spot: SENWSE Sec/Twnshp/Rge: 34-32S-33W
1618 feet from S Section Line, 1917 feet from E Section Line
Lease Name: MILDRED LEMERT Well #: 1
County: SEWARD Total Vertical Depth: 3070 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

COND Size: 20 feet: 60
PROD Size: 5.5 feet: 3069 WITH 650 SX CMT
SURF Size: 8.625 feet: 602

78
HPP

Well Type: SWD UIC Docket No: D19670.0 Date/Time to Plug: 03/17/2005 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RANDY GRAYSON Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/17/2005 12:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 500# HULLS AHEAD IN WATER. PUMP 300# HULLS MIXED IN CMT. PUMP 190 SX CMT DOWN 5 1/2". SHUT DOWN. PUMP 5 SX CMT DOWN BACKSIDE. PRESSURED TO 300 PSIG & SHUT IN. DROP HOSE INTO 5 1/2", CMT @ 350'+/-. FILL 5 1/2" TO SURFACE, STAYED FULL. TOTAL 215 SX CMT DOWN 5 1/2" & 5 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2526	3032		

RECEIVED
MAR 30 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
MAR 24 2005
KCC Dodge City

Signed Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 4-4-05
INV. NO. 2005061344

Form CP-213