



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-1103-21774-00-00

Dear Sir:

Mr. Merl Rogers of Drilling Oil Inc ^{W/c # 535} has this date requested permission to plug the following described well:

Operator's Full Name: Henry Brown Enterprises ^{W/c # 5537}

Complete Address: Drawer 340 Plainville, Kans. 67663

Lease Name: Oscmeyer Well No. # C-1

Location: 660' FSL - 660' FEL - SE Sec. 31 Twp. 6^S Rge. 19^W (E) (W)

County: Rooks Total Depth: 3264 FT

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Rogers was instructed to plug the well as follows:

8 5/8" 175 FT SP. CUC 1/130ST Comm - 2% GEL - 3% Ca-Cl. (Halliburton)
Order 170ST 50/50 Foamix 6% Gel - 3% Ca-Cl. and 8 5/8" Plug
spot with Drill Stem - with heavy mud Between all Plugs.
1ST Plug @ 930 FT 1/100ST ENT. 2ND Plug @ 240 FT 1/40ST ENT.
3RD Plug - Solid Bridge - Plug @ 40 FT 1/10ST ENT. 3 10ST In Rat Hole
10ST In Mouse Hole (circulate) (By Halliburton Ent)

RECEIVED
STATE CORPORATION COMMISSION
10-19-1982
OCT 19 1982

Very truly yours,
Marion Schmidt
Conservation Division Agent

CONSERVATION DIVISION
Wichita, Kansas