



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
10-25-1972
OCT 20 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-00272-00-00

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: T. W. Jackson,

Complete Address: Phillipsburg, Kansas.

Lease Name: Ostmeyer Well No. 1

Location: NW-NW-SW Sec. 31 Twp. 6 Rge. (E)(W) 19

County: Rooks Total Depth 3556' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

138'--8 5/8" Surface casing, cement circulated.
3545'--5 1/2" casing cemented on bottom with 175 Sx. Well plugged back to 3520'.
Top of perforations from 3357' to 3362'. Packer set @ 3285' with 2 joints tubing "Sanded In".

Sand well back to 3200' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

Conservation Division Agent