

State of Kansas



15-065-20071-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 14 1967
8-14-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Herb Mason of Dunne-Gardner Petroleum has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Dunne-Gardner Petroleum, Incorporated,

Complete Address: 300 Schweiter Building, Wichita, Kansas.

Lease Name: Jacobson Well No. 1

Location: NE-NE-NE Sec. 30 Twp. 6 Rge. (E)(W) 21

County Graham Total Depth 3827 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mason was instructed to plug the well as follows:

202'--8 5/8" Surface pipe, cement circulated with 135 Sx. Dakota section from 1140' to 1268'.

Circulate hole with heavy mud. Pull DP to 1300' and displace 100 Sx. cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

A. L. Nichols
Conservation Division Agent