

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-03 710-0000
API NUMBER 6/28/52

LEASE NAME Hindman

WELL NUMBER #1

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 36 TWP. 6 RGE. 20 (E) or (W)

COUNTY ROOKS

Date Well Completed 6/28/52

Plugging Commenced 5/24/00

Plugging Completed 5/24/00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kenny Brown Enterprises, LLC

ADDRESS P.O. Box 277 Hays, Ks. 67601-0277

PHONE# (785) 628-3384 OPERATORS LICENSE NO. 32250

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/23/00 (date)

by Richard Williams (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? YES

Producing Formation KC Depth to Top 3283 Bottom 3494 T.D. 3556

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
	surface	top	126	8 5/8	126	0
	production	top	3556	5 1/2	3556	0

JUN 1 2000

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Hooked up to 5 1/2 @ 2775 & pumped 40 sks SMD w/200# hulls. Pulled tubing to 1850' pump 40 sks SMD w/100 # hulls. Pulled tubing to 1850', pump 40 sks SMD w/200# hulls. Pulled tubing 925', pump 105 sks SMD circulate to surface w/200# hulls. Pulled tubing out of hole. Pump 6 bbl cement down 5 1/2. Did not fill up. Pump 30 sks cmt down 8 5/8. Closed in 8 5/8 w/75 PSI, let 5 1/2 set before topping off. Top off 5 w/5 sks cement. Job complete Swift Services, Inc.

Name of Plugging Contractor Swift Services, Inc. License No. _____

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kenny Brown Enterprises, LLC

STATE OF Kansas COUNTY OF Ellis, ss.


Steve Ruder

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Steve Ruder

(Address) P.O. Box 277



AND SWORN TO before me this 31st day of May, 2000

Charlotte Weber
Notary Public

My Commission Expires: 12-28-03

USE ONLY ONE SIDE OF EACH FORM

Form CP-
Revised 05-88

15-163-03710-0000

36-6-20.W

Rooks Co.

SWIFT Services, Inc.

DATE 5-24-00 PAGE NO.

JOB LOG

CUSTOMER Kenny Brown	WELL NO. 1	LEASE Hindman	JOB TYPE P.T.A	TICKET NO. 2365
-------------------------	---------------	------------------	-------------------	--------------------

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0945							ON LOC.
	1020		22		40			Hookup at 2775 & Pump 40SKS smc w/100 #hulls
								Pull Tbg To 1850'
			22		40			Pump 40SKS smc w/200 #hulls
								Pull Tbg To 925'
			58		105			Pump smc Cement 105 SKS circ to Surf. w/200 #hulls
	1230							Pull tbg out of hole
					10			Pump 6000 cmt down 5 1/2 csg did not fill
					30			Pump 30SKS cmt down 8 5/8
								Down in 8 5/8 w/ 75 PSI
								let 5 1/2 set before topping off
	1400				10			Top off 5 1/2 w/ 3SKS cmt
								205 SKS Down 5 1/2
								30 SKS Down 8 5/8
	1430							Job Complete

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 2000

CONSERVATION DIVISION
Wichita, Kansas

JOB LOG

SWIFT Services, Inc.

DATE 5-24-00 PAGE NO. 1

CUSTOMER Kenny Brown WELL NO. 1 LEASE Hindman JOB TYPE P.T.A TICKET NO. 2365

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0945							ON LOC.
	1020		22	40				Hookup at 2775 + Pump 40SKS SMD w/100 # hulls
								Pull Tbg To 1850'
			22	40				Pump 40SKS SMD w/200 # hulls
								Pull Tbg To 925'
			58	105				Pump SMD Cement 105 SKS circ to Surf. w/200 # hulls
	1230							Pull Tbg out of hole
				10				Pump 6BBC cmt Down 5 1/2 CSG DID NOT FILL
				30				Pump 30SKS cmt Down 3 5/8
								Close in 3 5/8 w/ 75 PSI
								Set 5 1/2 set before topping off
	1400			10				Top off 5 1/2 w/ 3FS cmt
								205 SKS Down 5 1/2
								30 SKS Down 3 5/8
	1430							Job Complete

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 2000
CONSERVATION DIVISION
Wichita, Kansas