

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 163-23,329-0000

LEASE NAME Carpenter

WELL NUMBER 1

1650 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 35 TWP. 6s RGE. 20w (Dist. W)

COUNTY Rooks

Date Well Completed 7/29/01

Plugging Commenced 12:00AM 7/29/01

Plugging Completed 2:15AM 7/29/01

RECEIVED

AUG. 17 2001

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KCC WICHITA BAIRD OIL COMPANY, LLC

ADDRESS P.O. Box 428 Logan, KS 67646-0428

PHONE# (785) 689-7456 OPERATORS LICENSE NO. 32819

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/27/01 (date)

by Roger Moses (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.O. 3700

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	227	8 5/8	226 89	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

1st Plug @ 1760' W/25sk 10sk In Mouse Hole Circulated 1st Plug 15 Minutes w/48Vis Mud
 2nd Plug @ 1120' W/100sk 15sk In Rat Hole Plugs displaced with mud
 3rd Plug @ 280' W/40sk Total 200sk 60/40poz 6%Gel w/4#FC/sk By Allied
 4th Plug @ 40' W/10sk Completed @ 2:15AM 7/29/01

Name of Plugging Contractor Discovery Drilling Co., Inc. License No. 31548

Address P.O. Box 763 Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BAIRD OIL COMPANY, LLC

STATE OF Kansas COUNTY OF Phillips, ss.


Jim R. Baird

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim R Baird

(Address) PO Box 428 Logan, KS 67646



before me this 14th day of August 2001

Robert B. Hartman
Notary Public

My Commission Expires: 3/29/03

OK