

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22,533
LEASE NAME Lewis
WELL NUMBER 1
SPOT LOCATION SE SW SE
SEC. 33 TWP. 6S RGE. 20 ~~XXXX~~ (W)
COUNTY Rooks
Date Well Completed 11-06-84
Plugging Commenced 11-06-84
Plugging Completed 11-06-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

Glenn M. Drotts d/b/a
LEASE OPERATOR G-D Oil Operations
ADDRESS 1105 E. 30th, Suite A, Hays, KS 67601

PHONE # (913) 625-5891 OPERATORS LICENSE NO. 9476

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6

Is ACO-1 filed? No if not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 3750' RTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		-0-	260'	8 5/8"	260'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Mud laden fluid 3750' - 1825' 10 sks cement @ Rathole
25 sks cement @ 1825'
100 sks cement @ 1150'
40 sks cement @ 250'
10 sks cement @ 40'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750
Address P. O. Box 506, Russell, KS 67665

RECEIVED

STATE OF KANSAS COUNTY OF RUSSELL, ss. STATE CORPORATION COMMISSION

Joe K. Branum (employee of operator) or NOV 08 1984
(operator) of above-described well, being first duly sworn on oath, says: That 11-8-84
I have knowledge of the facts, statements, and matters herein contained and CONSERVATION DIVISION
the log of the above-described well as filed that the same are true and Wichita, Kansas
correct, so help me God.

DENISE S. REYNOLDS
NOTARY PUBLIC
STATE OF KANSAS
My Appointment Expires:
2-13-85

(Signature) Joe K. Branum
(Address) P.O. Box 506, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 7th day of November, 19 84

My Commission expires: February 13, 1985 Denise S. Reynolds, Notary Public

15-163-22533-00-00

EMPHASIS OIL OPERATIONS

P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Glenn M. Drotts d/b/a
G-D Oil Operations
1105 E. 30th, Suite A
Hays, KS 67601

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, KS 67665

LEASE: Lewis WELL: 1

LOCATION: SE SW SE
Section 33-6S-20W
Rooks County, Kansas

ROTARY TOTAL DEPTH: 3750'

ELEVATION: 2226' K.B.

COMMENCED: 10-31-84

DATE COMPLETED: 11-07-84

CASING: 8 5/8" @ 260' with 160 sks cement

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Topsoil & sand	40'	Shale	3475'
Sand & Shale	1800'	Lime & Shale (RTD)	3750'
Anhydrite	1833'		


STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

Joe K. Branum
Joe K. Branum

Subscribed and sworn to before me this 7th day of November, 1984.

My Commission Expires: February 13, 1985.



Denise S. Reynolds
Denise S. Reynolds, Notary Public

RECEIVED
STATE CORPORATION COMMISSION

NOV 08 1984
11-8-84
CONSERVATION DIVISION
Wichita, Kansas

Handwritten notes:
12/2/84
11/8/84
3/5