

15-068-20239-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 19 Twp. 6S Rge. 22W (E) (W) X

Location as "NE/CNW/SW" or footage from lines C SW NW

Lease Owner Chief Drilling Co., Inc. - THREE G OIL, INC.

Lease Name Jacobs Well No. #1

Office Address Box 797, Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed July 4, 1969 19

Application for plugging filed July 4, 1969 19

Application for plugging approved July 4, 1969 19


Plugging commenced July 4, 1969 19

Plugging completed July 4, 1969 19

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3870 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	249	8 5/8"	249	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe at 1335' with 100 sacks

Plugged through drill pipe at 270' with 20 sacks

Plugged through drill pipe at 40' with 10 sacks

RECEIVED
STATE CORPORATION COMMISSION
JUL 9 1969
CONSERVATION DIVISION
Wichita, Kansas

7-9-69

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.

Address Box 797, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.


Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson

Box 797, Great Bend, Kansas 67530

(Address)

July 9, 1969



Clydene Williams Notary Public.

15-068-20239-00-00

WELL LOG

CHIEF DRILLING CO., INC.
Box 797
Great Bend, Kansas 67530

#1 JACOBS
C SW NW Sec. 19-6S-22W
Graham County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 6-26-69

Completed: 7-4-69

Casing Record: 8 5/8" set @ 249 w/185 sacks
60/40 Pozmix

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface clay	0	45	2420 Gr.
Shale & sand streaks	45	249	2422 D.F.
Shale & sand	249	1620	2425 K.B.
Sand	1620	1820	
Red bed & shale	1820	1980	
Red bed & shale	1980	2077	
Anhydrite	2077	2116	
Shale & shell	2116	2650	
Shale & lime	2650	3590	Anhydrite 2077 +348
Lime	3590	3610	RTD 3870-1445
Lime & shale	3610	3659	
Lime	3659	3765	
Lime & shale	3765	3830	
Lime	3830	3870	
T.D.	3870		

RECEIVED
STATE CORPORATION COMMISSION
JUL 9 1969
CONSERVATION DIVISION
Wichita, Kansas

FORMATION TOPS

STATE OF KANSAS, COUNTY OF BARTON) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SW NW of Section 19-6S-22W, Graham County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Office Mgr.

Subscribed and sworn to before me this 8th day of July, 1969.

Clydene Williams
Clydene Williams, Notary Public

My commission Expires: March 25, 1972

