

15-066-00202-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 18 Twp. 6 Rge. 22 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NE
Lease Owner Wood River Oil & Refining Co., Inc.
Lease Name Billips Well No. 1
Office Address 321 W. Douglas, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 2, 1951 19
Application for plugging filed February 1, 1951 Verbally 19
Application for plugging approved February 1, 1951 Verbally 19
Plugging commenced February 2, 1951 19
Plugging completed February 2, 1951 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 4002' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	267'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging Record

Filled hole with heavy mud to 240'. Wooden plug at 240'-15 sacks cement through drill pipe. Filled hole to 40' with heavy mud. Wooden plug at 40'-3 sacks hulls at 40'-10 sacks cement. Fill hole to bottom of cellar.



2-15-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to B & R DRILLING, INC.
Address RUSSELL, KANSAS

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
W. A. Michaelis, Jr. (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. A. Michaelis, Jr.
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of February, 1951

Notary Public signature

My commission expires 6-17-54

PLUGGING
FILE SEC 19 T 6 R 22
BOOK PAGE 59 LINE 45

Wood River Oil & Refining Co.
Billips No. 1

SW SW NE Sec. 18-6-22
Graham County, Kansas

Total Depth: 4002'
Comm: 1-19-51
Comp: 2- 2-51

Casing
8 5/8" Set @ 267'

Cement
160 Sacks of Monarch

Formation	Depth
Surface Soil-Shells-Shale	130
Shale-Shells	238
Shale	268
Shale-Shells	800
Shale-Sand-Pyrite	1165
Snad-Shale	1370
Sand	1390
Shale-Shells	1515
Shale-Shells-RedBed	1625
Sand	1800
Shale-RedRock	2020
Shale-Shells	2069
Anhydrite	2100
Shale-Lime	2455
Shale-Shells	2605
Sandy Lime(Broken)	2680
Shale-Lime	2905
Sandy Lime	2930
Lime-Shale	3435
Lime	3942
Shale-Lime	3985
Lime	4002'

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1951
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)SS
RUSSELL COUNTY)

2-15-51

I hereby certify that the above information is true and correct to the best of my knowledge.

Violet Leller

Subscribed and sworn to before me this 13th day of February, 1951.

Oliver Lamm

Notary Public

My commission expires: 6-17-54

PLUGGING
FILE SEC 18-6-22
BOOK PAGE 59-45