

4-041724

10-2

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-163-20,734-0001

NE NW SE \_\_\_\_\_ /4 SEC. 35, 06 S, 20 W  
2310 \_\_\_\_\_ feet from S section line  
1650 \_\_\_\_\_ feet from E section line

Operator license# 8914

Lease: Gartrell B Well # 1

Operator: H & C Operating, Inc.

County: Rooks

Address: P.O. Box 86  
Plainville, Kansas 67663

Well total depth 3685 <sup>119.76</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 245 feet  
W/190 sxs.

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 2 Month: October Year 1995

Plugging proposal received from: Bob Plante

Company: H & C Operating, Inc. Phone: \_\_\_\_\_

Were: 4 1/2" casing set at 3670' w/150 sxs cement. Perf. at 3215' - 3685'.  
Perf. anhy. at 1775' - Dakota at 1080'. Squeeze at 2115' - 2357' with 300 sxs cement.  
Ordered 225 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 300# hulls - plus 8 sxs gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All , Part [ ], None [ ]

Completed: Hour: 3:30 P.M., Day: 2, Month: October, Year: 1995

Actual plugging report: R.I.H. with tubing to 3250'. Spotted 40 sxs cement with 200# hulls, followed with 8 sxs gel. Pulled to 1800'. Circulated cement to surface with 80 sxs cement. P.O.O.H. with tubing. Squeezed 4 1/2" casing with 65 sxs cement. Max. P.S.I. 600#. R.U. cementers to 8 5/8" S.P. Squeezed 40 sxs cement with 100# hulls. Max. P.S.I. 200#. S.I.P. 100#.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 13 1995 10-13-95

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy.plug: CONSERVATION DIVISION  
Bottom plug(in place): YES , CALC , NO \_\_\_\_\_ Dakota plug: Wichita, Kansas NO \_\_\_\_\_  
Plugged through TUBING , CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ GL

I did  / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

INVOICED

DATE 10-17-95

INV. NO. 43811

1072