

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23329-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 35-6S-20W
1650 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: CARPENTER Well Number: 1
County: ROOKS Total Vertical Depth: 3700 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W. MAIN - PO BOX 428
LOGAN, KS 67646

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 227
Production: Size feet:
Liner: Size feet:

\$120.25

Well Type: DH UIC Docket No: Date/Time to Plug: 07/29/2001 12:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
According to KCC Rules & Regulations.

Plugging Proposal Received By: ROGER MOSES
Date/Time Plugging Completed: 07/29/2001 2:15 AM

WitnessType: Plugging Operations Were Not Witnessed
KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 227' w/150 sxs cement - Swift.
1st. Plug at 1760' w/25 sxs cement - Anhydrite.
2nd. Plug at 1120' w/100 sxs cement - Dakota Base.
3rd. Plug at 280' w/40 sxs cement - S.P. +50'.
4th. Plug at 40' w/10 sxs - 8 5/8" wiper plug.
15 sxs rathole.
10 sxs mousehole.
Total 200 sxs 60/40 pozmix - 6% gel - 1/4# flocele per sack.

RECEIVED

AUG - 8 2001

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

INVOICED

DATE

8-13-01

WIL. NO.

2002060211

District: 04

Signed

Roger J. Moses

(TECHNICIAN)

JD.

JUL 31 2001