

4-070173

15-163-03710-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-6-28-52

SE SE NE /4 SEC. 36, 06 S, 20 W
2970 feet from S section line
330 feet from E section line

Operator license# 32250

Lease: Hindman Well # 1

Operator: Kenny Brown Enterprises, LLC

County: Rooks 115.57

Address: 1602 E. 28th - Box 277
Hays, Kansas 67601 5/24

Well total depth 3556 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 9 5/8 Inch @ 126 feet

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Kenny Brown Enterprises, LLC License# 32250

Address: P.O. Box 277 - 1602 E. 28th St - Hays, Kansas 67601-0277

Company to plug at: Hour: 9:00 A.M. Day: 24 Month: May Year: 2000

Plugging proposal received from: Steve Ruder

Company: Kenny Brown Enterprises, LLC Phone: 785-628-3384

Were: 5 1/2" casing set at 3556'.

Perfs 3283' - 3483'.

Casing leaks from 800' - 1800'.

Ordered out 300 sxs Swift Multi-Density Cement with 500# hulls.

RECEIVED

STATE CORPORATION COMMISSION

JUN 1 2000

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All , Part , None

Completed: Hour: 2:00 P.M. Day: 24 , Month: May , Year: 2000

Actual plugging report: Ran tubing to top of fish 2775'. Swift pumped 40 sxs of Swift Multi-Density cement with 100# hulls. Pulled to 1850' and pumped 40 sxs with 200# hulls. Pulled to 925' and pumped 105 sxs with 200# hulls. Cement circulated. PTOH. Topped off with 20 sxs. Hooked up to backside and pumped 30 sxs with 100# hulls. Max. P.S.I. 100#. S.I.P. 100#.

Remarks Emergency plug orders given while rig over hole.

Condition of casing (in hole): GOOD BAD Anhy. plug: YES NO

Bottom plug (in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 2070 GL

I did / did not observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE 6/7/00

INV. NO. 61836

