

6 040611

API NUMBER 15- 163-21,165-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SENESE, SEC. 36, T. 6 S, R. 20 (W) (D)

1650 - feet from (S) section line
330 - feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5537

Lease Name Vehiga Well # 3

Operator: Kenny Brown Enterprises

County Rooks 118.63

Name & Address P.O. Drawer 340

Well Total Depth 3650 feet

Plainville, KS 67663

Conductor Pipe: Size - feet -

Surface Casing: Size 8 3/4 feet 166' w/ 130 sx

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Conty License Number _____

Address Hays, Ks 67601

Company to plug at: Hour 1:00 AM Day: 7 Month: 5 Year: 19 86

Plugging proposal received from Kenny Brown

(company name) K.B.E. (phone) _____

were: 4 1/2" csg set @ 3647' w/ 175 sx: perf @ 3200'-3600'

Fish in hole - Tbg top @ 910'

Sq. @ 780'-1240' w/ 300 sx & 1240' w/ 50 sx -

Ordered 150 sx 400 psg, 10% gel, 2 3/8 bit-mix (Econolite)

& 3 sx hulls

Plugging Proposal Received by Dennis J. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00 AM Day: 7 Month: 5 Year: 19 86

ACTUAL PLUGGING REPORT Impdn in 4 1/2" csg -> 70 sx Econolite w/

2 sx hulls. (36 bbls slurry) - MAX P.S.T. 850#

Shut-in 300#

Impdn 8 3/8" csg -> 50 sx Econolite (25 bbls slurry)

& 1 sx hulls. MAX 450#

Remarks: _____
(If additional description is necessary, use BACK of this form)

STATE CORPORATION COMMISSION
MAY 16 1986

CONSERVATION DIVISION
Wichita, Kansas
S-16-86 23
5-15-86

INVOICED
MAY 16 1986

Signed Dennis J. Hamel
(TECHNICIAN)

DATE _____
INV. NO. 13848