

8-14

4-041915

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-21,417 ⁰⁰⁻⁰⁰

NW NW SE /4 SEC. 36, 06 S, 20 W
2310 feet from S section line
2310 feet from E section line

Operator license# 5537

Lease: Vehige Well # 4

Operator: Viola E. Brown
d/b/a Kenny Brown Enterprises
Address: 400 N. Washington
P.O. Drawer 340
Plainville, Kansas 67663

County: Rooks 117.49
Well total depth 3615 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 168 Feet
W/135 sxs cmt.

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Halliburton Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00 A.M. Day: 14 Month: August Year 1997

Plugging proposal received from: Steve Ruder

Company: Kenny Brown Enterprises Phone: -

Were: 4 1/2" casing set at 3607' w/175 sxs cement. Perfs at 3294' - 3510'.
Anhy at 1675' - Salt at 2200' - Dakota at 980' - T.O.F. at 2100'.
Ordered 175 sxs mid-con two cement with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All , Part [] , None []

Completed: Hour: 3:30 P.M., Day: 14, Month: August, Year: 1997

Actual plugging report: Rigged-up cementers to 4 1/2" casing. Squeezed 135 sxs cement with 400# hulls. Max. P.S.I. 300#. 8 5/8" S.P. Squeezed 16 sxs mid con cement with 100# hulls. W.L.M. - additional 20 sxs cement to top off 4 1/2" casing.

Remarks: 8-27-97
Condition of casing (in hole): GOOD BAD _____ Anhy plug: YES NO _____
Bottom plug (in place): YES , CALC _____ , NO _____ Dakota plug: YES , NO _____
Plugged through TUBING _____ , CASING Elevation _____ G.L. _____

I did / did not [] observe the plugging.

INVOICED

DATE 8-29-97

INV. NO. 45878

Dennis Z Hamel
(agent)