

15-163-21870-06-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-21, 870  
NE, Sec. 35, T 6 S, R 20  
330 feet from N/S section line  
990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6278

Lease Name GOTTSCHALK Well # 2

Operator: PETX PETROLEUM CORP.  
Name & Address 1700 SECURITY LIFE BLDG.  
DENVER, CO. 80202

County TROOFS  
Well Total Depth 3700 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 254'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30 DRLLG. License Number #7 316-263-2043

Address 251 NORTH WATER #10 WICHITA, MO. 67202

Company to plug at: Hour: 12:30 PM Day: 14th Month: DEC Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO DICK DAVIS

(company name) H-30 DRLLG. (phone) 316-263-2043

were: 8 5/8" - 254' ES. CUL #175' 60% Pozmix - 2% GEL - 3% CA-CL. (BY ALLIED)

ORDER 180' 50% Pozmix 6% GEL - 3% CA-CL. AND 8 5/8" PLUG

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 1710' ES #20' CNT. -> 2nd PLUG @ 1020' ES #100' CNT. ST

3rd PLUG @ 270' ES #40' CNT. -> 4th PLUG SOLID BRIDGE HULLS - PLUG @ 40' #10' CNT.

10" IN RAT HOLE. (CIRCULATE) Signed M. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:00 PM Day: 14th Month: DEC Year: 1982

ACTUAL PLUGGING REPORT ORDERED 180' 50% Pozmix 6% GEL - 3% CA-CL. + 8 5/8" PLUG

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 1710' ES #20' CNT. -> 1020' ES #100' CNT. #/ST

3rd PLUG @ 270' ES #40' CNT. -> 4th PLUG SOLID BRIDGE HULLS - PLUG @ 40' #10' CNT.

10" IN RAT HOLE. (CIRCULATE)

(DID NOT FIND HRBUCKLE) CEMENTED BY ALLIED CNT.

Remarks: \_\_\_\_\_

RECEIVED STATE CORPORATION COMMISSION

DEC 21 1982 12-21-82

CONSERVATION DIVISION Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED  
DATE 1-25-83  
INV. NO. 2215-W

Signed M. Schmidt (TECHNICIAN)