

6 090321

MAY 25 1987

API NUMBER 15- 065-22,376 06-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW, SEC. 19, T 6 S, R 22

TECHNICIAN'S PLUGGING REPORT

1980 feet from S section line

3300 feet from E section line

Operator License # 8000

Lease Name Rogers 23-19 Well # 2

Operator: PanCanadian Petroleum Company

County Graham 129.35

Name & Address 600 17th Street, Suite 1800

Well Total Depth 3980 feet

Denver, Colorado 80201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor R and C. Drilling Co., Inc. License Number 9087

Address Box 296 Hays, Ks. 67601

Company to plug at: Hour: Day: 22 Month: May Year: 1987

Plugging proposal received from John Wise

(company name) R. C. Drilling Co., Inc. (phone)

were: Order 180 sks 60/40 pozmix, 6% gel and 8 5/8" wiper plug, spot all plugs
through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by Edwin A. Schumacher
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:30 AM Day: 25 Month: May Year: 19 87

ACTUAL PLUGGING REPORT 1st. plug 2100' with 20 sks

2nd plug 1320' with 100 sks and 1sk cello-flake

3rd plug 355' with 40 sks

4th plug 40' wiper plug and 10 sks

10 sks in rat hole

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1987
6-1-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Elevation - 2418' Anhydrite - 2084, ar buckle - no (Halliburton)
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-2-87

INV. NO. 17102

Signed Edwin A. Schumacher
(TECHNICIAN)
Edwin A. Schumacher