

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22335-00-00
Spot: NESE Sec/Twnshp/Rge: 19-6S-22W
1980 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: ROGERS 43-19 Well Number: 1
County: GRAHAM Total Vertical Depth: 3940 feet

Operator License No.: 30029
Op Name: STANDARD OPERATING COMPANY
Address: 100 S. MAIN STE 415
WICHITA, KS 67202

Conductor Pipe: Size feet: 3/28.05
Surface Casing: Size 8.625 feet: 302 205 sxs cmt
Production: Size 4.5 feet: 3939 515 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/17/2002 9:00 AM

Plug Co. License No.: 30029 Plug Co. Name: STANDARD OPERATING COMPANY

Proposal Rcvd. from: DAVID PAULY Company: STANDARD OPERATING COMPAN Phone: (316) 264-7566

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 500# hulls - 8 sxs gel.
D.V. Tool at 2069' w/350 sxs cement.

Plugging Proposal Received By: JAY PFEIFER

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/17/2002 12:30 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Tied onto annulus and pumped 15 sxs cement.
Swaged onto 4 1/2" - mixed and pumped 50 sxs cement with 500# hulls, followed by 8 sxs gel.
Topped with 100 sxs cement.
Max. P.S.I. 800#. S.I.P. 500#.

RECEIVED
OCT 22 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

OCT 18 2002

INVOICED

Form CP-2/3

DATE 10-22-02

INV. NO. 2003060693

replacement card.

19-06 -22W
C NE SE
PAN CANADIAN PETROLEUM COMPANY
DENVER, CO. 80201

#1 ROGERS 43-19 API 15-065-22335

site: 9-3/4 N & 1-1/2 E OF HILL CITY, KS
contr: MURFIN DRILLING
opd: J.E. HOLDEMAN

city: GRAHAM field: PENN EXT (1/4 S)
drig comp 12/07/86 card issued 02/05/87 last revised 03/02/88
fr date 10/24/86 spd date 11/30/86

ELV: 2399 KB LOG
tops.....depth/datum
SC.....2045 +354
TOP.....3408 -1009
HEEB.....3607 -1208
TOR.....3634 -1235
LANS.....3649 -1250
CONG.....3906 -1507
PBTD.....3896 -1497
RTD.....3940 -1541

IP status:

TEMP ABD,
CSG: 8-5/8" 302 / 205 SX, 4-1/2" 3939 / 515 SX
CORES TAKEN - DETAILS NA
DST (1) 3774-3810 (LANS I&J), / 15-45-30-30, REC 5'
DM, W / OIL SPKS ISIP 674# FSP 175# IFP 33# -35#
FFP 33# -33# IHP 1930# FHP 1922#

INFO RELEASED: 3/2/88 - ADDED WELL INFO

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS