

6 070921

00-00 208 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-22,626

SE NW NE, SEC. 18, T 6 S, R 22 (W) E

4290 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name GRIFFEY Well # 18-A-1

Operator: Ritchie Exploration, Inc.

County Graham 124.80

Name & Address 125 N. Market, Suite 1000

Well Total Depth 3840 feet

Wichita, Kansas 67202

Conductor Pipe: Size 0 feet

Jeff Christian

Surface Casing: Size 8 5/8 feet 288

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Inc. License Number 30606

Address Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 12th Month: May Year: 19 91

Plugging proposal received from Lloyd Dellett

(company name) Murfin Drilling Co. (phone) (316)-267-4375

were: 8 5/8" 288' S.P. cmt. w/ 220 sx. 60/40 poz. 2% Gel-3% Ca. Cl. (By Allied)

No ar buckle-Elv. 2386-Anhy 2060'-Mud Cond. 48 vis.-9.2 wt.-10 W.L.

Proposal 190 sx. 60/40 pozmix 6% Gel. 3% Cal.Cl.- 1 sx. Flo-Cele-Circulate hole.

Spot with drill stem-heavy mud betwten all plugs. No ar buckle.

25 sx. @ 2070'-100 sx. w/F.C. @ 1286'-40 sx. @ 330' - 10 sx. @ 40'

15 sx. rat hole (circulate)

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:45 P.M. Day: 12th Month: May Year: 19 91

ACTUAL PLUGGING REPORT Ritchie ordered 190 sx. 60/40 pozmix 6% Gel. 3% Ca.Cl. and

1 sx. Flo-Cele-circulated hole-spotted cement through drill stem. Heavy mud between all plugs.

1st plug @ 2070' w/25 sx. cmt.

4th plug @ 40' w/10 sx. cmt.

2nd plug @ 1286' w/100 sx. cmt. w/1 sx. F.C. 15 sx. rat hole (circulate)

3rd plug @ 330' w/40 sx. cmt.

Remarks: (If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION 5-30-91 MAY 30 1991

INVOICED

DATE 6-5-91

INV. NO. 32010

Jeb S.

Signed Marion J. Schmidt (TECHNICIAN)

CONSERVATION DIVISION Wichita, Kansas