

6 070524

PLUGGED

NOV 14 1986

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-22,333-00-00

C. NW- SW, SEC. 20, T. 6 S, R. 22 W

1980 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8000

Lease Name Brown Well # 13-20-1

Operator: PanCanadian Petroleum Co.

County Graham. 128.21

Name & Address P.O. Box 929

Well Total Depth 3945 feet

Denver, Colorado 80201

Conductor Pipe: Size 0 feet

J.O. Heisling

Surface Casing: Size 8 5/8 feet 301

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murphy Drilling Inc License Number 6023

Address Wichita, Kans. 67202

Company to plug at: Hour: 1:15 AM Day: 14 Month: Nov Year: 1986

Plugging proposal received from Forest Moore & Sons Delleke

(company name) PanCanadian Pet. and Murphy Drilling (phone) 303-825-8371

were: 8 5/8" 301 # SP. CUC #/205 Class 4. 3/8" OC

Proposal. 215 # 60/40 Formix 6% Cel. - 1 # 5/8" Plug

spot with Drill Stem, Recondition hole heavy mud between all plugs

Elv. 2393 - Ann. 2042' no circulation problems, mud emulsion, weight.

9.6 lbs, Viscosity 42, water loss 9.2, (25 # @ 3700) (25 # @ 2070)

(100 # @ 1290) (40 # @ 340) Plugging Proposal Received by Mauron Schmidt

(10 # Nuts, Plug Solid Bridge @ 40') 15 # Rat Hole (Circulate) (TECHNICIAN) By Eric Shellen

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 AM Day: 14 Month: Nov Year: 1986

ACTUAL PLUGGING REPORT Ordered 215 # 60/40 Formix 6% Cel. - 1 # 5/8" Plug,

and 8 5/8" Plug, spotted with Drill Stem, Recondition hole Heavy Mud

Between all plugs Displace first three (3) plugs with mud.

1st Plug @ 3700 ft #/25 # cnt, 2nd Plug @ 2070 ft #/25 # cnt

3rd Plug @ 1290 ft #/100 # cnt + 1 # 5/8" Plug, 4th Plug @ 340 ft #/40 # cnt

5th Plug ^{Solid Bridge} #/40 ft. to 0 #/10 # cnt, 15 # In Rat Hole (Circulate)

Remarks: Cemented by B.J. Titan

INVOICED

DATE 12-9-86

INV. NO. 15537

Witnessed by Albert Battagor

Signed Mauron Schmidt (TECHNICIAN) 11-21-86