

7-18

To: 6 070703
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,470 -00-00
NE NE SW, SEC. 24, T 6 S, R 22 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Keiswetter Well # 24C #1

Operator: Ritchie Exploration Inc.

County Graham 126.59

Name & Address 125 N. Market #1000

RECEIVED
STATE CORPORATION COMMISSION

Depth 3895 feet

Wichita, Ks. 67202

Conductor Pipe: Size 0 feet

Jeff Christian

Surface Casing: Size 8 5/8 feet 245

Abandoned Oil Well Gas Well SWD Well D&A X

OCT 21 1988
10-21-88
CONSERVATION DIVISION
Wichita, Kansas

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number

Address 125 N. Market #1000 Wichita, Ks. 67202

Company to plug at: Hour: PM Day: 18 Month: July Year: 19 88

Plugging proposal received from Lloyd Dellette

(company name) Murfin Drilling Co. (phone)

were: 8 5/8" - 245' S.P. cwc w/175 sks 60/40 Poz 3% Gel 2% Ca Cl (By Allied)

Arbuckle 3850' Elv. 2290' Anhy 1945' Mud condition 46 vis. 9.4 weight 10.0 water loss.

No circulation problems. Proposal 225 sks 60/40 Poz 6% Gel 3% Ca Cl 8 5/8" plug. Spot

with drill stem. Circulate. Heavy mud between all plugs. 25 sks at 3800'. 25 sks at

1960'; 100 sks w/1 sk F.C. at 1190'; 50 sks at 300'; 10 sks at 40'; 15 sks rathole (Cir)

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 12:45PM Day: 18 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Ordered 225 sks 60/40 Poz 6% Gel 3% Ca Cl and 8 5/8" plug.

Spotted with drill stem, circulated, mud between all plugs. 1st plug at 3800' w/25 sks

cement. 2nd plug at 1960' w/25 sks cement. 3rd plug at 1190' w/100 sks w/1 sk F.C.;

4th plug at 300' w/50 sks cement; 5th plug Hulls, plug 40' w/10 sks cement. 15 sks in

rathole (Cir) By Allied Cement.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
to observe this plugging.

DATE 10-26-88

INV. NO. 22724

Signed Marion J. Schmidt
Marion J. Schmidt