

6-100420

9-23

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,589 ⁻⁰⁰⁻⁰⁰
NE NE NE /4 SEC. 24, 06 S, 22 W
5250 feet from S section line
330 feet from E section line

Operator license# 4767 Lease Allen Worcester "B" well # 2

Operator: Ritchie Exploration, Inc. County Graham

Address: 125 North Market Well total depth 3870 feet ^{-125.77}
Suite 1000 Conductor Pipe: inch @ feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 255 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin drilling Company License# 6033

Address: Wichita, Kansas 67202

Company to plug at: Hour: ? Day: Month: Year:

Plugging proposal received from: Lloyd Dellett

Company: Murfin Drilling Company phone:

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

- 1st plug @ 3870 feet with 25 sacks Rat hole: 15 sacks
- 2nd plug @ 2000 feet " 25 " Mousehole: 10 sacks
- 3rd plug @ 1220 feet " 100 "
- 4th plug @ 300 feet " 40 "

5th plug @ 40 feet " wiper plug & 10 sx

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:00 am, Day: 23, Month: September, Year: 1990

Actual plugging report: Hole reported plugged as above.

Order 225sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2323 GL, Anhydrite depth: 1985 - 2023 feet

Did penetrate Arbuckle, cemented by Allied

I did observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION
11-15-90
NOV 15 1990

David K. Wann P.I.R.T. II
(agent)

Jeb S.

INVOICED

DATE NOV 16 1990

BILL NO. 29979