


15-065-19037-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County, Sec. 19 Twp. 6 Rge. 25 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines. SW SW SW  
Lease Owner John O. Farmer, Inc.  
Lease Name Brown #1 Well No. \_\_\_\_\_  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 5-13-59 19\_\_\_\_  
Plugging completed 5-19-59 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Fabricius  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4098 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	300'	none
				5-1/2"	3885'	1253'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 3830' and found it open.  
Filled w/sand to 3690' and dumped 3 sacks of  
cement with bailer. Pulled 5 1/2" casing, cleared  
hole and mudded the hole to 305', set 10' rock  
bridge to 295' and dumped 25 sacks of cement.  
Mudded the hole to 40', set 10' rock bridge and  
ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED  
STATE CORPORATION COMMISSION

MAY 27 1959

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Co., Inc. 5-27-59  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
I, Noel J. Knight (employee of owner) or (owner/lessee) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of May, 1959

9-27-62

Thomas V. Dwyer  
Notary Public.

My commission expires \_\_\_\_\_

PLUGGING  
FILE SEC 19 T 6 R 25 W  
BOOK PAGE 38 LINE 2