

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20212-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 4 1969
CONSERVATION DIVISION
Wichita, Kansas
4-4-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas,

Lease Name Wallace Well No. 1

Location CE/2-E/2-NW/4 Sec. 30 Twp. 6 Rge. (E) (W) 21

County Graham Total Depth 3871'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 2:15 AM Day 3 Month 4 Year 1969

The above well was plugged as follows:

330'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru
DP from 1100' to 775'. Pulled DP to 335' and displaced 20 Sx. cement thru DP from
335' to 275'. Pulled DP, set bridge @ 40' with 1/8 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/4/69

INV. NO. 9549-W

Signed: R. L. Pichal
Well Plugging Supervisor