

KANSAS

Form CP-3  
Rev. 6-26-62

**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

15-065-20071-00-00

RECEIVED  
STATE CORPORATION COMMISSION

AUG 14 1967  
8-14-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Dunne-Gardner Petroleum, Incorporated,

Complete Address: 300 Schweiter Building, Wichita, Kansas.

Lease Name Jacobson Well No. 1

Location NE-NE-NE Sec. 30 Twp. 6 Rge. (E) (W) 21

County Graham Total Depth 3827'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 3:30PM Day 8 Month 8 Year 1967

The Above well was plugged as follows:

202'--8 5/8" Surface pipe, cement circulated with 135 Sx.  
Dakota section from 1140' to 1268'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx.  
cement thru DP. Pulled DP to 210' and displaced 20 Sx. cement thru DP.  
Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 8/14/67

INV. NO. 6129-W