

AP

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

19-069-20235-0000

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Tilco et al,

Complete Address 815 Wichita Plaza Building, Wichita, Kansas.

Lease Name Emro Well No. 1

Location CNW-SW Sec. 21 Twp. 6 Rge. (E) (W) 21

County Graham Total Depth 3830'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated,

Address Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 8:00 AM Day 18 Month 6 Year 1969

The above well was plugged as follows:

198'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 880'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru
DP from 1100' to 775'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 140' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED JUN 23 1969
CONSERVATION DIVISION
Wichita, Kansas

Signed: M. L. F. Fichale
Well Plugging Supervisor

DATE 6/24/69
INV. NO. 9979-u

6-23-69