

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

15-068-02879-00-00

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 128-30  
LOCATION NW NE NE  
SEC. 9 TWP. 6 RGE. 22

Dry Hole          Abandoned Oil well   x   Abandoned Gas Well         

I have this date completed supervision of plugging of:

Well No. 1 Lease          Rush         

Operator Musgrove Pet Co Inc Address 518 Pet Bldg Wichita,

Field          County Graham

Total Depth 5701 Feet.

Plugging Contractor Jayhawk Pipe Pulling

Plugging Contractor's License No. 19

Address         

(Describe briefly the manner in which the well was plugged)

8 5/8" at 155' circulated with cement - 5 1/2" at 5701' with  
125 sax cement behind - Lane Wells plugs to 551' - perforations  
at 5508'.

Filled with sand to 5500', set 4 sax cement with dump bailer,  
pulled 2750' 5 1/2", filled with mud to 155', set rock and 15 sax  
cement, mud to 35', set rock and 10 sax cement to bottom  
cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT - 2 1953

*E. J. ...*  
District Conservation Agent

Date 9-30-53

PLUGGING  
FILE SEC 9 T 6 R 22 W  
BOOK PAGE 128 LINE 30

CONSERVATION DIVISION  
Wichita, Kansas

10-2-53