

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-30044-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1969

CONSERVATION DIVISION
Wichita, Kansas

7-28-69

Operator's Full Name E. H. Riggs,

Complete Address 350 Denver Club Building, Denver Colorado.

Lease Name LaCerte Well No. 4

Location CSE-SW Sec. 31 Twp. 6 Rge. (E) (W) 22

County Graham Total Depth 3870'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling, Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 2:00 PM Day 25 Month 7 Year 1969

The above well was plugged as follows:

222'--7" Od Surface casing, cement circulated with 110 Sx. (6 1/2" Hole).
3869'--4 1/2" Production casing cemented on bottom with 100 Sx. No plug back nor perforations indicated.

Pushed plug to 3650', sanded back to 3620' and set 3 Sx. cement with dump bailer.

Pulled 4 1/2" casing and squeezed well initially with 5 sacks hulls and 13 sacks gel and followed with 65 Sx. cement from 1100' to 775' then 9 sacks gel from 775' to 250' and followed with 25 Sx. cement from 250' to 175' then 2 sacks gel from 175' to 50' and finally 10 Sx. cement from 50' to bottom of cellar. Maximum pump-in pressure--350#.

Final shut-in pressure--100#. (Recovered 832'--4 1/2" casing.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 7/28/69

INV. NO. 167-W