

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-069-19029-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1964
10-12-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Wayne Merchant,
Complete Address: 227 Beacon Building, Wichita, Kansas.
Lease Name Stinemetz Well No. 1
Location CSE-NW Sec. 31 Twp. 6 Rge. (E) (W) 22
County Graham Total Depth 3756
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Murfin Drilling Company,
Address: 617 Union Center, Wichita, Kansas. License No.
Operation Completed: Hour 10:30PM Day 5 Month 10 Year 1964

The Above well, was plugged as follows:

208'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.
cement thru DP. Heavy mud to 180', set plug with 1/2 sack hulls and dis-
placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 10/12/64
INV. NO. 9964-W