

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-00268-00-01

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 28 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
7-28-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name E. H. Riggs,

Complete Address 350 Denver Club Building, Denver, Colorado.

Lease Name LaCerte Well No. 2

Location NW-NW-SW Sec. 31 Twp. 6 Rge. (E) (W) 22

County Graham Total Depth 3989'  
3989'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Company, Incorporated.

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 12:15 PM Day 25 Month 7 Year 1969

The above well was plugged as follows:

183'--8 5/8" Surface casing, cement circulated with 1 1/2 Sx.  
3989'--1 1/2" Production casing cemented on bottom with 100 Sx. No plug back nor perfor-  
ations indicated.

Pushed plug to 3650', built sand bridge to 3620' and set 3 Sx. cement with dump bailer.

Pulled 1 1/2" casing and squeezed well initially with 5 sacks hulls and 13 sacks gel and

followed with 100 Sx. cement from 1100' to 775' then 1 1/2 sacks gel from 775' to 220' and

followed with 20 Sx. cement from 220' to 160' then 3 sacks gel from 160' to 40' and

finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure--250#.

Final shut-in pressure--100#. (Mudding and cementing by Sun Cementing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/28/69

INV. NO. 166-W

Signed: [Signature]  
Well Plugging Supervisor