

KANSAS



CONSERVATION DIVISION AGENT'S REPORT

15-065-20303-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Rogers Well No. C-1

Location SW-NW Sec. 30 Twp. 6 Rge. (E) (W) 22

County Graham Total Depth 3855'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 2:00 PM Day 2 Month 2 Year 1970

The above well was plugged as follows:

237'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Sx. cement thru
DP from 1250' to 890'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED

FEB 6 1970

CONSERVATION DIVISION
Wichita, Kansas

Signed: M. L. Fitch
Well Plugging Supervisor

INVOICED

DATE 2/6/70
INV. NO. 1380-4

2-6-70