

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

75-163-20104-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
APR 29 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
4-29-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Shields Oil Producers, Inc.,

Complete Address: Russell, Kansas

Lease Name Irwin Well No. 1

Location NE NE NE Sec. 31 Twp. 6 Rge. 20 (E) (W) X

County Rooks Total Depth 3770'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Co. Tools

Address:      License No.     

Operation Completed: Hour 10 A Day 27 Month 4 Year 1968

The Above well was plugged as follows:

RTD 3770 8 5/8 csg set at 210' cwc. Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 900' and displaced 70 sc cem.  
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 4/29/68  
INV. NO. 7660-W