

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163-20251-00-00

RECEIVED 10-6-69  
STATE CORPORATION COMMISSION  
OCT 6 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Leo J. Dreiling Oil Co.

Complete Address Victoria, Kansas

Lease Name Davis Well No. 1

Location NE SE SE Sec. 32 Twp. 6 Rge. (E) (W) 20

County Rooks Total Depth 3695'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Co. Tools

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 3~~R~~ Day 4 Month 10 Year 1969

The above well was plugged as follows:

RTD 3695' 8 5/8 csg set at 216' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk cmt  
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/6/69

INV. NO. 590-W

Signed: Leo J. Messing  
Well Plugging Supervisor