

KANSAS

Form CP-3  
Rev. 6-4-68

*4*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20239-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 14 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
7-14-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Three G Oil, Incorporated,

Complete Address 1101 Wichita Plaza Building, Wichita, Kansas.

Lease Name Jacobs Well No. 1

Location SW-NW Sec. 19 Twp. 6 Rge. (E) (W) 22

County Graham Total Depth 3870'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Chief Drilling Company, Incorporated,

Address Box #797, Great Bend, Kansas, License No. \_\_\_\_\_

Operation Completed: Hour 8:00 PM Day 1 Month 7 Year 1969

The above well was plugged as follows:

2491--8 5/8" Surface casing, cement circulated with 185 Sx.  
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 100 Sx. cement thru  
DP from 1325' to 1000'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from  
275' to 215'. Pulled DP, set bridge @ 140' with  $\frac{1}{2}$  sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. S. Nichols  
Well Plugging Supervisor

DATE 7/14/69  
INV. NO. 91-w