



15-069-20239-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 14 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 7-14-69

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drilling, Co., Inc., has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Three G Oil, Incorporated,

Complete Address: 1101 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Jacobs Well No. 1

Location: SW-NW Sec. 19 Twp. 6 Rge. (E)(W) 22

County: Graham Total Depth 3870' Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Burris was instructed to plug the well as follows:

249'--8 5/8" Surface casing, cement circulated with 185 Sx.  
Top of Dakota section @ 1100'.

Circulate hole with heavy mud. Pull DP to 1325' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*W. S. Nichols*

Conservation Division Agent