

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: VESS OIL CORPORATION
 Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226
 Phone: (316) 682-1537 Operator License #: 5030
 Type of Well: oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: _____ (Date)
 by: _____ (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3468 Bottom: 3482 T.D. 3482
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-03462-00-00
 Lease Name: Hall B
 Well Number: #15
 Spot Location (QQQQ): _____ - NE - NE - SW
1320' 2310 Feet from North / South Section Line **KCC BEM**
2970' Feet from East / West Section Line **4-6.05**
 Sec. 26 Twp. 11S S. R. 17W East West **RBDms**
 County: Ellis
 Date Well Completed: 9/16/40
 Plugging Commenced: 3/17/05
 Plugging Completed: 3/17/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1060'	
				5-1/2"	3468'	
				sqzd	1095'	150 sx
				sqzd	2455'	300 sx

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Plugged and abandoned as follows: MIRU. TIH w/tbg to 3380'. Pumped down tubing with 15 sx gel w/50 sx 60/40 poz w/10% gel and 300# hulls on bottom. Pull tubing to 1500'. Circulated cement to surface w/80 sx cement w/300# hulls. TOH. Tied onto 5 1/2" casing and pumped 60 sx and good cement to surface up 8 5/8" casing. Pumped 35 sx cement and SI w/400#.

Name of Plugging Contractor: Allied Cementing Co., Inc. License #: 99996
 Address: P.O. Box 31, Russell, KS 67665-0031
 Name of Party Responsible for Plugging Fees: Vess Oil Corporation
 State of Kansas County, Sedgwick, ss.

Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 5th day of April
Michelle D. Hennig My Commission Expires _____
 Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
APR 06 2005
KCC WICHITA

Bm

WELL RECORD

Company Citizen Service Oil Co. Well No. 15 Farm Hall #B
 Location 330' south & 330' west of Center Sec. 26 T. 11 R. 17-W
 Elevation 2012 County Ellis State Kansas
 Drlg. Comm. August 24, 1940 Contractor Mabee Oil & Gas Company
 Drlg. Comp. September 16, 1940 Acid 1500 gallons Sept. 17, 1940
 T. D. 3482' Initial Prod. Boho-Meter Potential: 9753 oil, 0 water, 24 hrs.

CASING RECORD:

8-5/8" @ 1060' con. 300 sx Monarch
 and 10 sx Aquagel
 5-1/2" @ 3468' con. 100 sx Ideal

Corr. Top Artuckle 3468 (-1456)
 Penetration 14'
 Total Depth 3482

FORMATION RECORD:

shale & shells 0-605
 sand 620
 shale & shells 780
 sand 855
 shale 860
 sand & shale 890
 shale 920
 red bed, shale & shells 1060
 red bed & shells 1205
 lime 1214
 anhydrite 1245
 shale & shells 1575
 shale & salt 1750
 shale & lime 1940
 lime broken 1987
 lime & shale 2205
 lime 2290
 shale & shells 2325
 lime 2365
 shale & shells 2526
 lime & shale 2646
 shale & shells 2740
 lime 2785
 lime & shale 2808
 shale 2895
 lime broken 2935
 shale 2958
 lime 3205
 broken lime 3288
 lime 3340
 lime & shale 3388
 lime 3402
 lime & shale 3430
 lime broken 3472
 lime (top Artuckle 3472½) 3472½
 3472½ Net. T.D. = 3488 S.L.M.
 lime 3468-3482 T.D.

Fillup: 700' oil in 1 hr.
 1350' oil in 2 hrs.
 1825' oil in 2-3/4 hrs.
 2325' oil in 4 hrs.
 2800' oil in 6 hrs.

Syfe: 500' 0°
 1500' 0°
 2000' 0°
 2500' 0°
 3000' 0°

RECEIVED
 APR 06 2005
 KCC WICHITA

ALLIED CEMENTING CO., INC. 18596

Federal Tax I.D.# XXXXXXXXXX

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Russell

DATE <u>3-17-05</u>	SEC.	TWP.	RANGE	CALLED OUT <u>8:00 Am</u>	ON LOCATION <u>9:30 Am</u>	JOB START	JOB FINISH <u>12:30 PM</u>
LEASE <u>HALL</u>	WELL # <u>B-15</u>	LOCATION <u>Cole RR Rd Jct 285 IE 15</u>			COUNTY <u>Ellis</u>	STATE <u>K</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR

TYPE OF JOB plug

HOLE SIZE	T.D.
CASING SIZE <u>5 1/2</u>	DEPTH
TUBING SIZE <u>2 3/8</u>	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

OWNER

CEMENT

AMOUNT ORDERED
250 lbs 60/40-10
600 # Halls Used 225 lbs

COMMON	<u>135</u>	@	<u>8.30</u>	<u>1120.5</u>
POZMIX	<u>90</u>	@	<u>4.50</u>	<u>405.</u>
GEL	<u>34</u>	@	<u>13.00</u>	<u>442.</u>
CHLORIDE		@		
ASC		@		
Halls	<u>6</u>	@	<u>20.00</u>	<u>120.</u>

RECEIVED				
APR 06 2005				
KCC WICHITA				
HANDLING	<u>290</u>	@	<u>1.50</u>	<u>435.0</u>
MILEAGE	<u>.055/mi</u>			<u>510.4</u>
TOTAL				<u>3032.</u>

EQUIPMENT

PUMP TRUCK # <u>366</u>	CEMENTER <u>Bill</u>
	HELPER <u>Glen</u>
BULK TRUCK # <u>213</u>	DRIVER <u>Keith</u>
BULK TRUCK #	DRIVER

SERVICE

DEPTH OF JOB	
PUMP TRUCK CHARGE	<u>570.00</u>
EXTRA FOOTAGE	@
MILEAGE <u>32</u>	@ <u>4.50</u> <u>144.00</u>
MANIFOLD	@
	@
	@
TOTAL <u>714.</u>	

REMARKS:

Tubing @ 3400 mix 157 lbs gel
Follow w/ 50 lbs Cont w/ 300 # Halls
pull to 1500 mix 80 lbs w/ 300 # Halls
CIRC. TO SURFACE pull tubing
pump down 5' w/ 60 lbs conc to
surface on backside pump 35 lbs
press to 400 # SHAFT

CHARGE TO: Vess

STREET _____

CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

PLUG & FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	
TOTAL		
TAX		
TOTAL CHARGE		
DISCOUNT		IF PAID IN 30 DAY
PRINTED NAME		
PRINTED NAME		